

NOTES

- A.** SEE "STANDARDS FOR TAPS, SERVICES AND METERS" FOR TYPICAL NOTES.
- B.** BACKFLOW PREVENTION DEVICE REQUIRED--CONTACT WATER METER DEPARTMENT FOR APPROVED DEVICE.
- C.** PROVIDE APPROVED DRAIN FOR IRRIGATION SYSTEM.
- D.** ALTERNATE DESIGNS MUST BE SUBMITTED FOR APPROVAL.
- E.** THE CURB BOX MUST BE BROUGHT UP TO FINISH GRADE.
- F.** NO OUTLETS ARE ALLOWED BETWEEN METER AND THE BACKFLOW PREVENTER OR HOSE BIBB VACUUM BREAKER WITH THE EXCEPTION OF ONE SCREW PLUG-IN TAP FOR WINTERIZING/DRAINAGE PURPOSES.
- G.** THE UNDERGROUND WATER SERVICE SHALL BE TYPE K COPPER OR BLUE REHAU MUNICIPEX TYPE SDR 9 CTS (200 PSI RATING), FROM THE METER PIT UP TO THE BACKFLOW PREVENTER OR HOSE BIBB VACUUM BREAKER.
- H.** THE INSTALLATION SHALL BE INSPECTED BY THE CITY.

**INSTRUCTIONS FOR
THE INSTALLATION OF IRRIGATION METERS
AND
BACKFLOW PREVENTERS FOR IRRIGATION**

- A.** MAKE DRAWING OF THE PROPOSED IRRIGATION SYSTEM. THIS DRAWING MUST BE APPROVED BY CITY AND SHELBY COUNTY HEALTH DEPARTMENT.
- B.** ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CITY "STANDARDS FOR TAPS, SERVICES AND METERS".
- C.** GET THE NECESSARY PERMITS.
1) TAPPING FEE
- D.** GET FORMS AT SHELBY COUNTY HEALTH DEPARTMENT FOR EACH BACKFLOW PREVENTER TO BE INSTALLED, PRIOR TO DOING THE WORK.
- E.** AFTER THE BACKFLOW PREVENTERS HAVE BEEN INSTALLED, PLEASE FILL OUT THE FORMS COMPLETELY WITH THE OWNER/LEASEHOLDER'S NAME, ADDRESS (WHERE THE BACKFLOW PREVENTER WAS INSTALLED), LOCATION OF THE BACKFLOW PREVENTER, SIZE, MAKE, MODEL, TEST RESULTS BY A LICENSED PLUMBER, ANNUAL TEST RESULTS THERE AFTER, AND SERIAL NUMBER OF THE BACKFLOW PREVENTER. PLEASE RETURN THE COMPLETED FORMS TO THE CITY.
- F.** CONTACT BOTH CITY AND THE SHELBY COUNTY HEALTH DEPARTMENT AFTER THE WORK HAS BEEN COMPLETED. BACKFLOW PREVENTERS HAVE TO BE INSPECTED BY BOTH CITY AND THE SHELBY COUNTY HEALTH DEPARTMENT.
- G.** SEPARATE VALVES, ONE BEFORE AND AFTER, MUST BE PLACED NEAR THE BACKFLOW PREVENTER WHENEVER THE EXISTING BACKFLOW IS REMOVED.
- H.** IRRIGATION METERS MUST BE PLACED OUTSIDE IN A DUAL METER PIT.



**CITY OF
SIDNEY**

**STANDARD INSTALLATION FOR IRRIGATION
METERS AND BACKFLOW PREVENTER**

REVISIONS:
07-22-13

DATE

APPROVED:
FEB. 2002

PAGE No.

800-17