



- ① ITEM 608, 5" CONCRETE WALK, AS PER PLAN APPLY 2 COATS OF SUPER DIAMOND CLEAR CURING AND SEALING COMPOUND, OR APPROVED EQUIVALENT PER MANUFACTURER'S RECOMMENDATION ON ALL SURFACES INCLUDING BACK OF CURB IMMEDIATELY AFTER FINISHING SURFACES.
- ② ITEM 411, 8" AGGREGATE BASE, (IN 2 EQUAL 4" LIFTS), SATURATED W/ WATER PRIOR TO COMPACTION
- ③ ITEM SPECIAL, BRICK PAVING, WALK (2-1/4" BRICK), (REFER TO CITY FOR SPECIFICATIONS)
- ④ 3/4" ROLLED BITUMINOUS SETTING BED. (REFER TO VILLAGE FOR SPECIFICATIONS)
- ⑤ ITEM 608, 4" CONCRETE UNDERLAYMENT, CURE & SEAL WITH ONE COAT OF SUPER DIAMOND CLEAR, OR ODOT APPROVED CURING COMPOUND.
- ⑥ ITEM 411, 5-3/4" AGGREGATE BASE SATURATE W/ WATER PRIOR TO COMPACTION
- ⑦ ITEM 204, SUBGRADE COMPACTION
- ⑧ ITEM 407, TACK COAT @ 0.10 GAL/S.Y. NEOPRENE MODIFIED ASPHALT.
- ⑨ NEOPRENE MODIFIED ASPHALT ADHESIVE.

BRICK TYPICAL SECTION

(REFER TO SPECIFICATIONS)